BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2020-21/OW/WORK_INDENT45975/CALL-3

NAME OF WORK: Providing Name boards and stickring and labelling in Bagalagunte in ward no 14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor PILLAPPA GIRIJA SHANKAR	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Supply and fixing of Retro Reflective Single Arrow Road Name Sqm Signboard of size 1600mm x 900mm made out of retro reflective sheeting conforming to Type XI standards of ASTM D 4956 - 09 & as per IRC 67-2012 for full back ground of blue colour & white letters and fixed over 4 mm thick Aluminium Composite Material sheet having minimum 0.5 mm thick Aluminium skin on both sides with back side painted grey colour and fixed over back support frame SS angle of 15mm x 20mm x 1.2mm, supported by 38mm OD stainless steel pipe all round in 304 grade and 2 nos of vertical posts of 50 mm OD stainless steel pipe of 202 grade firmly fixed to the ground by means of properly designed foundation of size 450mm x 450mm x 600mm in 1:1.5:3 ratio cement concrete. The background shall be blue in color with letters and border in white, the item includes earthwork excavation, cost of all materials, loading, unloading, lead, lift, transportation etc., complete, as per direction of engineer incharge of work clause 6.9 of IRC 67-2012 for Type XI retro reflective sheeting from the sheeting manufacturer & a certified copy of test reports from an independent test laboratory conforming to clause 6.7 of IRC 67 2012 including outdoor weather exposure	Sqm	185.00	14094.82	Rupees Fourteen Thousand Ninety Four and Eighty Two Paise Only

P. Giri Shanky
Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor,

Scanned with CamScanner